



ALL INDIA INSTITUTE OF MEDICAL SCIENCES, BATHINDA

NEAR GIANI ZAIL SINGH COLLEGE, JODHPUR ROMANA, DABWALI ROAD-151001

Invitation of quotations for the work Provision of Water Point and Urinals at SICU-2, IPD, at AIIMS Bathinda

Reference No.: AIIMS Bathinda/Engg. & Estate/24-25/4575

Dated: 18 June 2025

Notice for Invitation of quotations

Sealed Quotations are invited on behalf AIIMS, Bathinda for the subject work at AIIMS Bathinda as per terms & conditions mentioned below. The filled quotations along with all the required documents must reach in the office of the undersigned on or before **30th June 2025 (Monday), 17:00 hrs. (Date & Time)**. The **Envelope containing the quotation** must be sealed and **super scribed as under: -**

“Invitation of quotations for the work Provision of Water Point and Urinals at SICU-2, IPD, at AIIMS Bathinda”– Department of Engineering & Estate”

The Quotation should be sent to the address: -

The Executive Director
AIIMS Bathinda,
Mandi Dabwali Road,
Punjab - 151001.

Terms & Conditions:

1. The quotations received **after this deadline or unsealed shall not be entertained** under any circumstances whatsoever. In case of postal delay this Institute will not be responsible. The offer submitted by Fax / email shall not be considered and no correspondence will be entertained in this matter.
 - (i) AIIMS Bathinda Reserve the right to cancel quotation without any information.
2. Quotations must be in the **enclosed prescribed Performa (BoQ) on the letterhead of the firm duly signed** by the Proprietor/ Partner/ Director or their authorized representative, in case of signing of quotation by the authorized representative letter of authorization must be attached with the quotation.
3. The supplier should supply and installed all the items.
4. Rates must be quoted in Indian rupees. Rates must be inclusive of **all charges** (including Freight charges, taxes, etc.). **No overwriting or cutting** is permitted in the rate. If found, the quotation shall be summarily rejected.
5. The **rates quoted must be valid for 90 days minimum from the date of opening of the quotation** and silence of any tendered on this issue shall be treated as agreed with this condition.
6. **Total cost/amount will be taken in consideration for L1.** Becoming L1 will not be the criteria for awarding of purchase order unless the rates are reasonable & justified.
7. The firm/agency may satisfy the following conditions: -
 - (i) The firm shall have valid GST/Other taxes and IT PAN.
 - (ii) The firm should not be black listed by any Government agency/Department.

8. Quantity may increase or decrease as per the decision of the competent authority of AIIMS Bathinda.
9. **Work Completion period** – within 30 days from Purchase order or as per work order awarded.
10. **Payment Terms:** Payment will be only after satisfactorily execution of the work and after inspection by the AIIMS Bathinda. Payment will be done after verification of the work done by the engineering wing. No advance payment shall be admissible.
11. Unsealed quotations, quotations received after due date, quotations not superscribed as mentioned above, unsigned quotations are liable to be rejected. No queries regarding the same shall be entertained in this office. Quotations received through email, fax, telegram etc. shall not be entertained.
12. The decision of AIIMS Bathinda on all matters concerning this work shall be final and binding on the party submitting the quotation.
13. **Defect Liability Period:** DLP shall be of 03 month from completion date of the work.
14. To ensure the compliance during the **DLP period, 05% of the amount shall be withheld** from each bill of the contractor and that will be released after completion of the DLP period.
15. If the contractor does not start the work within the scheduled time, the contractor shall be debarred from participating in future tender of the Institute as per the respective clause of the Manual for Procurement of Works.
16. The work shall required to be executed as per the CPWD specifications. Substandard material/ work shall be rejected. Replacement of the same be done within 03 days from the issue of the notice, otherwise the contractor shall be liable to be penalized.
17. **LIQUIDATED DAMAGES:** - The successful bidder must start the work within 7 days of issuance of Letter of Commencement of work and complete the work within the time frame as stipulated by the AIIMS Bathinda, failing which, AIIMS Bathinda will recover Compensation for Delay of work @ .5 % per week or part of the week of delayed of the total amount of work (accepted Tendered Value of work) which may be recovered from bill/Performance Security/Security Deposit of the contractor. The total amount of compensation for delay to be paid under this condition shall not exceed 5 % (Five percent) of the Accepted tendered value of work. The said work can also be executed under the Risk and Cost of the Contractor with prior intimation of 15 days based upon the performance of the contractor.
18. **STATUTORY DEDUCTIONS:** - All the statutory deductions towards GST/Income Tax etc. shall be made from the bill/s as applicable as per the prevailing rates under the rules. TDS as applicable will be deducted from each bill of the contractor under the statutory rules of the

Union Govt., in respect of Income Tax and other taxes. No claim on account of any other statutory charges for execution of work awarded under this contract will be entertained by AIIMS Bathinda and such charges should be paid by the contractor himself.

19. **INDEMNIFICATION:** - AIIMS Bathinda shall have no liability whatsoever towards the persons deployed by the contractor for the subject of work. The contractor shall keep AIIMS Bathinda indemnified against all losses/damages/liabilities/claims arising out of deployment of the contractor's workers during the period of the contract. Any claim which may arise during the currency of the contract or at any subsequent point of time shall be the sole responsibility of the contractor and AIIMS Bathinda shall in no way be held responsible for it.

20. **LIABILITY AGAINST LOSS OR DAMAGE TO LIFE OR PROPERTY:** - The contractor shall be liable to pay AIIMS Bathinda for any loss/damage caused because of theft/pilferage of any property of AIIMS Bathinda from the premises where the staffs of the contractor have been deployed, provided such loss/damage is due to the negligence of the contractor or its deployed manpower which shall be deducted from Security deposit/Performance Guarantee if not paid. The contractor shall also be liable for the consequences of any incident of major/minor injury or accident or death caused to any of its worker arising out of or in the course of his employment under the scope of the contract. AIIMS Bathinda shall not be responsible for any injury or loss of life in respect of the contractor that may take place while on work. Any compensation or expenditure towards treatment for such injury or loss of life shall be the sole responsibility of the contractor. The contractor shall be solely responsible for any damage, injury or accident that may occur to any of his personnel working under his contract. No claim whatsoever arises to AIIMS Bathinda.

Sd/-
Executive Engineer (Civil),
AIIMS Bathinda

Check List

S. No.	Particulars	Whether attached	Remarks
1	GST certificate	YES / NO	
2	PAN Card	YES / NO	
3	Non-Blacklisting Undertaking on letter head	YES / NO	
4	All the documents mentioned above and the quotation document has been signed & stamped	YES /NO	

BOQ

Name of Work: the work Provision of Water Point and Urinals at SICU-2, IPD, at AIIMS Bathinda

Sr. No.	Description	Unit	Quantity	Rate	Amount
1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 meters lead				
	For thickness of 10 to 25 mm	Sqm	10		
2	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge				
	Nominal concrete 1:3:6 or richer mix (including equivalent design mix)	Cum	2		
3	Dismantling of flushing cistern of all types (C.I./PVC/Vitrious China) including stacking of useful materials near the site and disposal of unserviceable materials within 50 metres lead.	Each	5		
4	Providing and fixing up to floor five level precast cement concrete string or lacing courses, copings, bed plates, anchor blocks, plain window sills, shelves, louvers, steps, stair cases, etc., including hoisting and setting in position with cement mortar 1:3 (1 Cement: 3 coarse sand), cost of required Centering complete.				
	1:1.5:3 (1 cement: 1.5 coarse sand(zone-III) derived from natural sources: 3 graded stone aggregate 20 mm nominal size derived from natural sources)	Cum	0.5		
5	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300 mm or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS: 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick Cement Mortar 1:4 (1 Cement: 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including pointing the joints with white cement and matching pigments etc., complete.	sqm	5		
6	Providing and fixing soil, waste and vent pipes:				
	100 mm dia				
	Sand cast iron S&S pipe as per IS: 1729	Meter	10		
7	Providing and fixing CP Brass Single lever telephonic wall mixer of quality				
	15 mm nominal dia	Each	5		
8	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete :				
	25 to 40 mm nominal bore	Each	7		

9	Making connection of drain or sewer line with existing manhole including breaking into and making good the walls, floors with cement concrete 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) cement plastered on both sides with cement mortar 1:3 (1 cement : 3 coarse sand), finished with a floating coat of neat cement and making necessary channels for the drain etc. complete				
	For pipes 100 to 250 mm diameter	Each	5		
10	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings and fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc.				
	15 mm nominal dia Pipes	m	30		
11	Providing and fixing CP Brass 32 mm size Bottle Trap of approved quality & make and as per the direction of Engineer-in-charge	each	2		
12	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931				
	15 mm nominal bore	each	4		
13	Providing and fixing Ist quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	Sqm	10		
14	Providing and fixing white vitreous china battery based infrared sensor operated urinal of approx. size 610 x 390 x 370 mm having pre & post flushing with water (250 ml & 500 ml consumption), having water inlet from back side, including fixing to wall with suitable brackets all as per manufacturers specification and direction of Engineer-in-charge.	Each	2		
15	Providing and fixing Polyvinyl Chloride (PVC) pipes, having thermal stability for hot & cold water supply, including all PVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step PVC solvent cement and testing of joints complete as per direction of Engineer in Charge.				
I	Internal work - Exposed on wall				
	40mm	m	5		
	63mm	m	6		
II	PVC elbow	each	8		
III	Brass elbow 15mm	each	22		

IV	Floor Trap	each	2		
V	Brass Gate valve				
	15mm	each	10		
VI	C P trap Grating (Jali) 80 mm(With/Without waste Hole)	Each	1		
VII	Dismantling and Refixing washbasin	Each	1		
VIII	CPVC Brass MTA 15mm	Each	20		
IX	CPVC Union 15mm	Each	10		
Total					
GST@18%					
Grand Total					