



ALL INDIA INSTITUTE OF MEDICAL SCIENCES, BATHINDA

Mandi Dabwali Road, Bathinda, Punjab – 151001.

Invitation of quotations for Supply and Installation of False Ceiling at EHS Clinic in OPD Hall, AIIMS Bathinda

Reference No.: AIIMS Bathinda/Engg./26-27/5605

Dated:16 July 2026

Notice for Invitation of quotations

Sealed Quotations are invited on behalf AIIMS, Bathinda for the subject work at AIIMS Bathinda as per terms & conditions mentioned below. The filled quotations along with all the required documents must reach in the office of the undersigned on or before **27th July 2026 (Monday), 17:00 hrs. (Date & Time)**. The **Envelope containing the quotation** must be sealed and **super scribed as under: -**

***“Invitation of quotations for
Supply and Installation of False Ceiling at EHS Clinic in OPD Hall,
AIIMS Bathinda’– Department of Engineering”***

The Quotation should be sent to the address: -

The Executive Director
AIIMS Bathinda,
Mandi Dabwali Road, Bathinda
Punjab - 151001.

Terms & Conditions:

1. Quotations must be in the **enclosed prescribed Performa (BoQ) on the letterhead of the firm duly signed** by the Proprietor/ Partner/ Director or their authorized representative, in case of signing of quotation by the authorized representative letter of authorization must be attached with the quotation.
(i) AIIMS Bathinda Reserve the right to cancel quotation without any information.
2. **Make/Model:-**
(i) The Vendor has to supply make mentioned in BoQ.
(ii) The supplier should supply and installed all the items.
3. Rates must be quoted in Indian rupees. Rates must be inclusive of **all charges** (including Freight charges, taxes, etc.). **No overwriting or cutting** is permitted in the rate. If found, the quotation shall be summarily rejected.
4. The **rates quoted must be valid for 90 days minimum from the date of opening of the quotation** and silence of any tendered on this issue shall be treated as agreed with this condition.
5. **Total cost/amount will be taken in consideration for L1.** Becoming L1 will not be the criteria for awarding of purchase order unless the rates are reasonable & justified.
6. The firm/agency may satisfy the following conditions: -
(i) The firm shall have valid GST/Other taxes and IT PAN.
(ii) The firm should not be black listed by any Government agency/Department.

7. Quantity may increase or decrease as per the decision of the competent authority of AIIMS Bathinda.
8. **Work Completion period** – within 30 days from Purchase order or as per work order awarded.
9. **Payment Terms:** Payment will be only after satisfactorily execution of the work and after inspection by the AIIMS Bathinda. Payment will be done after verification of the work done by the engineering wing. No advance payment shall be admissible.
10. Unsealed quotations, quotations received after due date, quotations not superscribed as mentioned above, unsigned quotations are liable to be rejected. No queries regarding the same shall be entertained in this office. Quotations received through email, fax, telegram etc. shall not be entertained.
11. The decision of AIIMS Bathinda on all matters concerning this work shall be final and binding on the party submitting the quotation.
12. If the contractor does not start the work within the scheduled time, the contractor shall be debarred from participating in future tender of the Institute as per the respective clause of the Manual for Procurement of Works.
13. The work shall required to be executed as per the CPWD specifications. Substandard material/ work shall be rejected. Replacement of the same be done within 03 days from the issue of the notice, otherwise the contractor shall be liable to be penalized.
14. **LIQUIDATED DAMAGES:** - The successful bidder must start the work within 03 days of issuance of Letter of Commencement of work and complete the work within the time frame as stipulated by the AIIMS Bathinda, failing which, AIIMS Bathinda will recover Compensation for Delay of work @ .5 % per week or part of the week of delayed of the total amount of work (accepted Tendered Value of work) which may be recovered from bill/Performance Security/Security Deposit of the contractor. The total amount of compensation for delay to be paid under this condition shall not exceed 5 % (Five percent) of the Accepted tendered value of work. The said work can also be executed under the Risk and Cost of the Contractor with prior intimation of 15 days based upon the performance of the contractor.
15. **STATUTORY DEDUCTIONS:** - All the statutory deductions towards GST/Income Tax etc. shall be made from the bill/s as applicable as per the prevailing rates under the rules. TDS as applicable will be deducted from each bill of the contractor under the statutory rules of the Union Govt., in respect of Income Tax and other taxes. No claim on account of any other statutory charges for execution of work awarded under this contract will be entertained by AIIMS Bathinda and such charges should be paid by the contractor himself.
16. **INDEMNIFICATION:** - AIIMS Bathinda shall have no liability whatsoever towards the

persons deployed by the contractor for the subject of work. The contractor shall keep AIIMS Bathinda indemnified against all losses/damages/liabilities/claims arising out of deployment of the contractor's workers during the period of the contract. Any claim which may arise during the currency of the contract or at any subsequent point of time shall be the sole responsibility of the contractor and AIIMS Bathinda shall in no way be held responsible for it.

17. **LIABILITY AGAINST LOSS OR DAMAGE TO LIFE OR PROPERTY:** - The contractor shall be liable to pay AIIMS Bathinda for any loss/damage caused because of theft/pilferage of any property of AIIMS Bathinda from the premises where the staffs of the contractor have been deployed, provided such loss/damage is due to the negligence of the contractor or its deployed manpower which shall be deducted from Security deposit/Performance Guarantee if not paid. The contractor shall also be liable for the consequences of any incident of major/minor injury or accident or death caused to any of its worker arising out of or in the course of his employment under the scope of the contract. AIIMS Bathinda shall not be responsible for any injury or loss of life in respect of the contractor that may take place while on work. Any compensation or expenditure towards treatment for such injury or loss of life shall be the sole responsibility of the contractor. The contractor shall be solely responsible for any damage, injury or accident that may occur to any of his personnel working under his contract. No claim whatsoever arises to AIIMS Bathinda.

Sd/-
Assistant Engineer (Civil),
AIIMS Bathinda

Check List

S. No.	Particulars	Whether attached	Remarks
1	GST certificate	YES / NO	
2	PAN Card	YES / NO	
3	Non-Blacklisting Undertaking on letter head	YES / NO	
4	All the documents mentioned above and the quotation document has been signed & stamped	YES /NO	

BOQ					
S.No	Description	Unit	Quantity	Rate	Amount
1	Providing and fixing GI Clip in Metal Ceiling System of 600x600 mm module which includes providing and fixing 'C' wall angle of size 20x30x20 mm made of 0.5 mm thick pre painted steel along the perimeter of the room with help of nylon sleeves and wooden screws at 300 mm center to centre, suspending the main C carrier of size 10x38x10 mm made of G.I steel 0.7 mm thick from the soffit with help of soffit cleat 37x27x25x1.6 mm, rawl plugs of size 38x12 mm and C carrier suspension clip and main carrier bracket at 1000 mm c/c. Inverted triangle shaped Spring Tee having height of 24 mm and width of 34 mm made of GI steel 0.45 mm thick is then fixed to the main C carrier and in direction perpendicular to it at 600 mm centers with help of suspension brackets. Wherever the main C carrier and spring T have to join, C carrier and spring T connectors have to be used. All sections to be galvanized @ 120 gms/sqm (both side inclusive), fixing with clip in tiles into spring T with :				
	GI Metal Ceiling Clip in plain Beveled edge global white color tiles of size 600x600 and 0.5 mm thick with 25 mm height, made of G I sheet having galvanizing of 100 gms/ sqm (both sides inclusive) and 20% perforation area with 1.8 mm dia holes and having NRC of 0.5, electro statically polyester powder coated of thickness 60 microns (minimum), including factory painted after bending and perforation.	Sqm	50		
2	Providing and fodng carbon steel galvanised (minimum coating 5 micron) dash fastener of 10 mm dia double threaded 6.8 grade (yield strength 480 N/mm2), counter sunk head, comprising of 10 mm dia polyamide PA 6 grade sleeve, including drilling of hole in frame, concrete masonry, etc. as per direction of Engineer-in-charge.				
	10 x 120 mm	Each	36		
3	Steel work in built up tubular (round, square or rectangular hollow tubes ec.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.				
	Hot finished welded type tubes	kg	1000		
4	Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (both side inclusive) as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm centre, with 25mm long dry wall screws @ 230 mm interval, including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25 mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound , jointing tapes , finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the Engineer in Charge but excluding the cost of painting with :				
	12.5 mm thick tapered edge gypsum plain board conforming to IS: 2095- (Part I) :2011 (Board with BIS certification marks)	Sqm	70		
5	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	Sqm	60		
6	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour.				
	Two coats	Sqm	60		
7	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :				
	Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture	Sqm	80		
Total					
GST@18%					
Total Amount					

NOTE - The rates shall be inclusive of supply of material and transportation charges