ALL INDIA INSTITUTE OF MEDICAL SCIENCES, BATHINDA

Mandi Dabwali Road, Bathinda, Punjab – 151001.

Invitation of quotations for

Work of construction of Patient Shelter Shed near Emergency at AIIMS Bathinda

Reference No.: AIIMS Bathinda/Engg./26-27/5992

Dated: 13 Nov. 2026

Notice for Invitation of quotations

Sealed Quotations are invited on behalf AIIMS, Bathinda for the subject work at AIIMS Bathinda as per terms & conditions mentioned below. The filled quotations along with all the required documents must reach in the office of the undersigned on or before **20th Nov 2026 (Friday), 17:00 hrs. (Date & Time)**. The **Envelope containing the quotation** must be sealed and **super scribed as under**: -

"Invitation of quotations for

Work of construction of Patient Shelter Shed near Emergency at

AIIMS Bathinda – Department of Engineering"

(a) The Quotation should be sent to the address: -

The Executive Director
AIIMS Bathinda,
Mandi Dabwali Road, Bathinda
Punjab - 151001.

(b) Physical Submission:

Place the quotation in the box at Central Dak Office, C Block, First Floor, Medical College Building, AIIMS Bathinda, after getting the receipt date stamp from the Central Dak official.

Terms & Conditions:

1. Quotations must be in the **enclosed prescribed Performa *(BoQ)* on the letterhead of the firm duly signed** by the Proprietor/ Partner/ Director or their authorized representative, in case of signing of quotation by the authorized representative letter of authorization must be attached with the quotation.

(i) AIIMS Bathinda reserve the right to cancel quotation without any information.

2. **Make/Model:-**

(i) The Vendor has to supply make mentioned in BoQ.

(ii) The supplier should supply all the items.

(iii) Defective/Faulty Items: Any item found damaged, defective, faulty, or not conforming to the prescribed specifications at the time of supply, inspection, or during the validity of the supply order shall be replaced by the Contractor with a new and conforming item free of cost, without any additional financial liability to the Department. The replacement shall be carried out within the stipulated time as directed by the Engineer-in-Charge.

3. Rates must be quoted in Indian rupees. Rates must be inclusive of **all charges** (including Freight charges, taxes, etc.). **No overwriting or cutting** is permitted in the rate. If found, the quotation shall be summarily rejected.

4. The **rates quoted must be valid for 90 days minimum from the date of opening of the quotation** and silence of any tendered on this issue shall be treated as agreed with this condition.

5. **Total cost/amount will be taken in consideration for L1.** Becoming L1 will not be the criteria for awarding of purchase order unless the rates are reasonable & justified.

6. The firm/agency may satisfy the following conditions: -
   (i) The firm shall have valid GST and PAN.
   (ii) The firm should not be black listed by any Government agency/Department.

7. Quantity may increase or decrease as per the decision of the competent authority of AIIMS Bathinda.

8. **Work Completion period** – within 30 days from Purchase order/ Work Order or as per the terms of the work order to be awarded to the successful bidder.

9. **Payment Terms**: Payment will be only after satisfactorily execution of the work and after inspection by the AIIMS Bathinda. Payment will be done after verification of the work done by the engineering wing. No advance payment shall be admissible.

10. Unsealed quotations, quotations received after due date, quotations not superp scribed as mentioned above, unsigned quotations are liable to be rejected. No queries regarding the same shall be entertained in this office. Quotations received through email, fax, telegram etc. shall not be entertained.

11. The decision of AIIMS Bathinda on all matters concerning this work shall be final and binding on the party submitting the quotation.

12. If the contractor does not start the work within the scheduled time, the contractor shall be debarred from participating in future tender of the Institute as per the respective clause of the Manual for Procurement of Works.

13. The work shall required to be executed as per the CPWD specifications. Substandard material/ work shall be rejected. Replacement of the same be done within 03 days from the issue of the notice, otherwise the contractor shall be liable to be penalized.

14. **LIQUIDATED DAMAGES: -** The successful bidder must start the work within 03 days of issuance of Letter of Commencement of work and complete the work within the time frame as stipulated by the AIIMS Bathinda, failing which, AIIMS Bathinda will recover Compensation for Delay of work @ .5 % per week or part of the week of delayed of the total amount of work (accepted Tendered Value of work) which may be recovered from bill/Performance Security/Security Deposit of the contractor. The total amount of compensation for delay to be paid under this condition shall not exceed 5 % (Five percent) of the Accepted tendered value of work. The said work can also be executed under the Risk and Cost of the Contractor with prior

intimation of 15 days based upon the performance of the contractor.

15. **STATUTORY DEDUCTIONS: -** All the statutory deductions towards GST/Income Tax etc. shall be made from the bill/s as applicable as per the prevailing rates under the rules. TDS as applicable will be deducted from each bill of the contractor under the statutory rules of the Union Govt., in respect of Income Tax and other taxes. No claim on account of any other statutory charges for execution of work awarded under this contract will be entertained by AIIMS Bathinda and such charges should be paid by the contractor himself.

16. **INDEMNIFICATION: -** AIIMS Bathinda shall have no liability whatsoever towards the persons deployed by the contractor for the subject of work. The contractor shall keep AIIMS Bathinda indemnified against all losses/damages/liabilities/claims arising out of deployment of the contractor's workers during the period of the contract. Any claim which may arise during the currency of the contract or at any subsequent point of time shall be the sole responsibility of the contractor and AIIMS Bathinda shall in no way be held responsible for it.

17. **LIABILITY AGAINST LOSS OR DAMAGE TO LIFE OR PROPERTY: -** The contractor shall be liable to pay AIIMS Bathinda for any loss/damage caused because of theft/pilferage of any property of AIIMS Bathinda from the premises where the staffs of the contractor have been deployed, provided such loss/damage is due to the negligence of the contractor or its deployed manpower which shall be deducted from Security deposit/Performance Guarantee if not paid. The contractor shall also be liable for the consequences of any incident of major/minor injury or accident or death caused to any of its worker arising out of or in the course of his employment under the scope of the contract. AIIMS Bathinda shall not be responsible for any injury or loss of life in respect of the contractor that may take place while on work. Any compensation or expenditure towards treatment for such injury or loss of life shall be the sole responsibility of the contractor. The contractor shall be solely responsible for any damage, injury or accident that may occur to any of his personnel working under his contract. No claim whatsoever arises to AIIMS Bathinda.

-Sd/-
Assistant Engineer (Civil),
AIIMS Bathinda

Check List			
S. No.	**Particulars**	**Whether attached**	**Remarks**
1	GST certificate	YES / NO	
2	PAN Card	YES / NO	
3	Non-Blacklisting Undertaking on letter head	YES / NO	
4	All the documents mentioned above and the quotation document has been signed & stamped	YES /NO	

BOQ					
Name of work :- Construction of Patient shelter near Emergency at AIIMS Bathinda					
Sr. No.	**Description of Items**	**Unit**	**Quantity**	**Rate**	**Amount**
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.				
	All kind of soil	Cum	10		
2	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	Cum	4		
3	Centering and shuttering including strutting, propping etc. and removal of form for all heights				
	Foundations, footings, bases of columns, etc. for mass concrete	Sqm	4		
4	P&Laying in position machine batched and machine mixed design mix M-25 grade cement concrete for reinforced ….. As per direction of Engineer -in-charge..(Note:- cement content considered in this items is @ 330 kg/cum. " Excess/less cement used as per design mix is payable/recoverable separately).				
	All level upto plinth level				
	Concrete of M25 grade with minimum cement content of 330 kg /cum	Cum	2		
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
	1:4:8 (1 Cement : 4 coarse sand (zone-111) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	Cum	6.00		
6	Brick work with common burnt clay F.P.S (non mudular) bricks of class designation 7.5 in superstructure above plinth level upto floor V level in all shapes and sizes in:				
	Cement mortar 1:4 (1 cement : 4 coarse sand)	Cum	4.5		
7	12 mm cement plaster of mix :				
	1:4 (1 cement: 4 coarse sand)	Sqm	21.00		
	20 mm cement plaster of mix :				
	1:4 (1 cement: 4 coarse sand)	Sqm	22.00		

8	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.				
	Hot finished welded type tubes	Kg	850		
9	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	Sqm	115		
Total amount without GST					
GST @ 18%					
Total amount with GST					